

STANDARD BID CONDITIONS

M-09-107H

1. **ACCEPTANCE AND REJECTION:** The Arkansas State Highway and Transportation Department (AHTD) reserves the right to reject any or all bids, to accept bids in whole or in part (unless otherwise indicated by bidder), to waive any informalities in bids received, to accept bids on materials or equipment with variations from specifications where efficiency of operation will not be impaired, and to award bids to best serve the interest of the State.
2. **PRICES:** Unless otherwise stated in the Bid Invitation, the following will apply: (1) unit prices shall be bid, (2) prices should be stated in units of quantity specified (feet, each, lbs., etc.), (3) prices must be F.O.B. destination specified in bid, (4) prices must be firm and not subject to escalation, (5) bid must be firm for acceptance for 30 days from bid opening date. In case of errors in extension, unit prices shall govern. Discounts from bid price will not be considered in making awards.
3. **BID BONDS AND PERFORMANCE BONDS:** If required, a **Bid Bond** in the form of a cashier's check, certified check, or surety bond issued by a surety company, in an amount stated in the Bid Invitation, must accompany bid. **Personal and company checks are not acceptable as Bid Bonds.** Failure to submit a Bid Bond as required will cause a bid to be rejected. The Bid Bond will be forfeited as liquidated damages if the successful bidder fails to provide a required Performance Bond within the period stipulated by AHTD or fails to honor their bid. Cashier's checks and certified checks submitted as Bid Bonds will be returned to unsuccessful bidders; surety bonds will be retained. The successful bidder will be required to furnish a **Performance Bond** in an amount stated in the Bid Invitation and in the form of a cashier's check, certified check, or surety bond issued by a surety company, unless otherwise stated in the Bid Invitation, as a guarantee of delivery of goods/services in accordance with the specifications and within the time established in the bid. **Personal and company checks are not acceptable as Performance Bonds.** In some cases, a cashier's check or certified check submitted as a Bid Bond will be held as the Performance Bond of the successful bidder. Cashier's checks or certified checks submitted as Performance Bonds will be refunded shortly after payment has been made to the successful bidder for completion of all terms of the bid; surety bonds will be retained. Surety bonds must be issued by a surety company authorized to do business in Arkansas, and must be signed by a Resident Local Agent licensed by the Arkansas State Insurance Commissioner to represent that surety company. Resident Agent's Power-of-Attorney must accompany the surety bond. Certain bids involving labor will require Performance Bonds in the form of surety bonds only (no checks of any kind allowed). In such cases, the company issuing the surety bond must comply with all stipulations herein and must be named in the U. S. Treasury listing of companies holding Certificates of Authority as acceptable sureties on Federal Bonds and as acceptable reinsuring companies. Any excess between the face amount of the bond and the underwriting limitation of the bonding company shall be protected by reinsurance provided by an acceptable reinsuring company. Annual Bid and Performance Bonds on file with E & P Division must have sufficient unencumbered funds to meet current bonding requirements, or the bid will be rejected, unless the balance is submitted as set forth above, prior to bid opening.
4. **TAXES:** The AHTD is not exempt from Arkansas State Sales and Use Taxes, or local option city/county sales taxes, when applicable, and bidders are responsible to the State Revenue Department for such taxes. These taxes should not be included in bid prices, but where required by law, will be paid by the AHTD as an addition thereto, and should be added to the billing to the AHTD. The AHTD is exempt from Federal Excise Taxes on all commodities except motor fuels; and excise taxes should not be included in bid prices except for motor fuels. Where applicable, tax exemption certificates will be furnished by the AHTD.
5. **"ALL OR NONE" BIDS:** Bidders who wish to bid "All or None" on two or more items shall so stipulate on the face of bid sheet; otherwise, bid may be awarded on an individual item basis.
6. **SPECIFICATIONS:** Complete specifications should be attached for any substitution or alternate offered, or where amplification is necessary. Bidder's name must be placed on all attachments to the bid.
7. **EXCEPTIONS TO SPECIFICATIONS:** Any exceptions to the bid specifications must be stated in the bid. Any exceptions to manufacturer's published literature must be stated in the bid, or it will be assumed that bidder is bidding exactly as stated in the literature.
8. **BRAND NAME REFERENCES:** All brand name references in bid specifications refer to that commodity or its equivalent, unless otherwise stated in Bid Invitation. Bidder should state brand or trade name of item being bid, if such name exists.
9. **FREIGHT:** All freight charges should be included in bid price. Any change in common carrier rates authorized by the Interstate Commerce Commission will be adjusted if such change occurs after the bid opening date. Receipted common carrier bills that reflect ICC authorized rate changes must be furnished.
10. **SAMPLES, LITERATURE, DEMONSTRATIONS:** Samples and technical literature must be provided free of any charge within 14 days of AHTD request, and free demonstrations within 30 days, unless AHTD extends time. Failure to provide as requested within this period may cause bid to be rejected. Samples, literature and demonstrations must be substantially the same as the item(s) being bid, unless otherwise agreed to by AHTD. Samples that are not destroyed will be returned upon request at bidders expense. Samples from successful bidders may be retained for comparison with items actually furnished.
11. **GUARANTY:** Unless otherwise indicated in Bid Invitation, it is understood and agreed that any item offered or shipped on this bid shall be newly manufactured, latest model and design, and in first class condition; and that all containers shall be new, suitable for storage or shipment and in compliance with all applicable laws relating to construction, packaging, labeling and registration.
12. **BACKORDERS OR DELAY IN DELIVERY:** Backorders or failure to deliver within the time required may constitute default. Vendor must give written notice to the AHTD, as soon as possible, of the reason for any delay and the expected delivery date. The AHTD has the right to extend delivery if reasons appear valid. If reason or delivery date is not acceptable, vendor is in default.
13. **DEFAULT:** All commodities furnished will be subject to inspection and acceptance by AHTD after delivery. Default in promised delivery or failure to meet specifications authorizes the AHTD to cancel award or any portion of same, to reasonably purchase commodities or services elsewhere and to charge full increase, if any, in cost and handling to defaulting vendor. Applicable bonds may be forfeited.
14. **ETHICS:** *"It shall be a breach of ethical standards for a person to be retained, or to retain a person, to solicit or secure a State contract upon an agreement of understanding for a commission, percentage, brokerage, or contingent fee, except for retention of bona fide employees or bona fide established commercial selling agencies maintained by the contractor for the purpose of securing business."* (Arkansas Code, Annotated, Section 19-11-708).

ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT

NOTICE OF NONDISCRIMINATION

The Arkansas State Highway and Transportation (Department) complies with the Americans with Disabilities Act of 1990, Section 504 of the Rehabilitation Act of 1973, Title VI of the Civil Rights Act of 1964 and other federal equal opportunity laws and therefore does not discriminate on the basis of race, sex, color, age, national origin, religion or disability, in admission or access to and treatment in Department programs and activities, as well as the Department's hiring or employment practices. Complaints of alleged discrimination and inquiries regarding the Department's nondiscrimination policies may be directed to James B. Moore, Jr., Section Head - EEO/DBE (ADA/504/Title VI Coordinator), P. O. Box 2261, Little Rock, AR 72203, (501) 569-2298, (Voice/TTY 711), or the following email address:

james.moore@arkansashighways.com.

This notice is available from the ADA/504/Title VI Coordinator in large print, on audiotape and in Braille.

ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT

SPECIFICATION 09-64-9100

FOR

**TRUCK MOUNTED TELESCOPIC AERIAL LIFT AND BODY
WITH SIGN STORAGE COMPARTMENT**

1. **General:** This specification is intended to cover a sign storage compartment, service body, and a pedestal mount, two section, hydraulic operated, telescoping boom and work platform, with a minimum working height of 34', completely mounted on a truck chassis and ready for use.
2. **Sign Storage Compartment:** Shall have a sign storage compartment mounted between service body and cab of truck. Sign storage compartment to be built and installed using the attached drawings as a guide. Doors shall have heavy duty handles and locks keyed alike. The actual overall width of the compartment shall be the width of the service body.
3. **Service Body:** Shall be standard height service body normally designed to mount on a cab and chassis with dual rear tires and 60" CA measurement.
 - A. **Construction:** Electrically welded all steel construction with edges rolled or folded. Body shall have longitudinal members and cross members welded for floor support. Body floor shall be constructed of no less than 12 gauge safety tread plate.
 - B. **Dimensions:**
 - (1) **Body Length:** 108" – 110".
 - (2) **Body Width:** 93" – 96". (Alternate width may be provided if required for compatibility with overall width of chassis furnished.)
 - (3) **Body Height:** 39 ½", minimum.
 - (4) **Body Floor To Compartment Top:** 25 ½" minimum.
 - (5) **Compartment Depth:** 18", minimum.
 - (6) **Floor Width:** 50" – 55". (Alternate width may be provided if required for compatibility with overall width of chassis furnished.)
 - C. **Compartments:** Each side of the body shall have a minimum of one (1) vertical compartment in front of the rear wheels, one (1) horizontal compartment over the rear wheels and a minimum of one (1) vertical compartment behind the rear wheels. Vertical compartments shall be full height and have adjustable shelves. Each horizontal compartment shall have an adjustable shelf and dividers. All doors shall be protected from weather and have double panels with flush type handles and locks keyed alike. Doors shall have rubber seals to keep out water and dust.
 - D. **Bumper:** Rear of body shall have a combination bumper and tail shelf which extends no less than 1" past the work platform when boom is cradled.
 - E. **Mud Flaps:** Shall have mud flaps no less than 24" wide and 1/4" thick, without advertising, mounted behind rear wheels.
 - F. **Lights:** Combination tail and directional lights and backup lights to meet ICC regulations.
4. **Aerial Lift:**
 - A. **Pedestal:** Shall be mounted in bed of truck directly behind sign storage compartment to allow for full use of body space. Shall have a hydraulic motor driven rotator providing 360° continuous rotation.
 - B. **Boom:** Shall be pedestal mount, telescoping type with a minimum of two (2) sections. Horizontal reach from centerline of rotation shall be no less than 21'. Height from ground to bottom of work platform at full extension shall be no less than 29'. Shall have a total boom travel of no less than 80° above horizontal to no less than 6° below horizontal. Shall have a support at rear of truck to cradle the boom with an additional support to rest the work platform during road travel.
 - C. **Controls:** Shall have two (2) sets of elevation, extension and rotation controls. One set to be mounted at end of boom and one set of controls mounted on pedestal with the capability of over-riding boom controls if necessary. Controls shall be full pressure, full feathering type with a single handle (joy-stick) control on the boom. Shall have engine start and stop controls at the platform.

- D. Platform: Shall be end hung type equipped with a hydraulic leveling system. Shall also be equipped with hydraulic rotator providing a minimum of 180° rotation to allow the platform to be placed on either side of the boom. Shall be constructed of metal with approximate dimensions of 24" x 24" x 41". Shall have a side access opening equipped with a gate or safety chain and be rated for a load of no less than 300 pounds. A safety belt with lanyard to secure belt to platform shall be provided.
- E. Stabilization: Shall be accomplished by means of torsion bar and counterweight as required by manufacturer. Unit shall be tested and certification shall be furnished that unit can be operated on level ground with the platform loaded to 150% of rated capacity, and on a 5° slope with the platform loaded to 133% of rated capacity, without lifting any tire from ground.
- F. Outriggers: In addition to the normal stabilization specified above, the unit shall have individually controlled, hydraulically powered, "A" type outriggers located at front area of service body and mounted at or behind the pedestal. The outriggers may intrude into the front compartment on each side of the service body, if necessary. Outriggers which extend vertically, or "out and down" outriggers are not acceptable. Outriggers to be equipped with pivoting type pads.
- G. Hydraulic System: Shall have elevation cylinder, hydraulically actuated telescoping boom and hydraulically actuated boom rotator. All cylinders shall be double acting. Hydraulic system shall have by-pass valve to prevent overloading and shall have safety device whereby load will remain suspended in case of power or pressure failure.
- (1) Hydraulic Tool Circuit: Shall have an open center type hydraulic tool circuit with outlets at the work platform and at right rear corner of truck bed for operation of hydraulic drills, sign post drivers, etc. Outlets shall be equipped with quick couplers. Circuit shall supply 10 - 12 gpm at 1800 - 2000 psi.
 - (2) Power Take-Off: Shall be mounted on truck transmission, with flange bracket for direct mounting to hydraulic pump. Shall have a pilot light to indicate when PTO is engaged.
 - (3) Hydraulic Pump: Shall be direct mounted to power-take-off on truck transmission and be of adequate capacity to operate all functions of the aerial lift plus the hydraulic tool circuit specified above.
5. Cab & Chassis:
- A. GVWR: 25,500 pounds, minimum.
 - B. Wheelbase: Minimum of 150", maximum of 160".
 - C. Cab to Axle: 84", nominal.
 - D. Engine: Liquid cooled turbocharged diesel with a minimum piston displacement of 6.7 liters developing no less than 230 SAE gross horsepower at rated RPM and no less than 620 lb. ft. SAE gross torque. Shall have a minimum governed speed of 2,400 RPM. (The following engines are acceptable: Cummins ISB, International MaxxForce DT (DT466), Isuzu 6H, Mercedes MBE900. If an alternate engine is proposed, it must be approved by AHTD prior to bid opening.) Shall have full flow oil filter(s), fuel filters, dry type air cleaner, 12 volt electrical equipment with no less than 100 amp alternator and maintenance free batteries as regularly furnished with engine specified. Engine shall be equipped with a block heater which will operate on 120 volts AC.
 - (1) Exhaust System: Horizontal exhaust. The exhaust system may need to provide clearance for PTO installation, depending on which side of the transmission the installer chooses to mount the PTO.
 - (2) Engine Shutdown: Engine safety shutdown system with manual or automatic override to include the following features: low oil pressure - warning bell/buzzer plus shutdown, high coolant temperature - warning bell/buzzer plus shutdown and low coolant level - warning bell/buzzer plus light or shutdown.
 - (3) Cooling System: As recommended and regularly furnished by the manufacturer for use with the engine size specified above, with anti-freeze protection to -20° F, or lower.
 - (4) Block Heater: Engine shall be equipped with a block heater which will operate on 120 volts AC.
 - E. Transmission: Allison 2500 RDS automatic with five (5) or six (6) speed programming and PTO provision. Transmission shall have synthetic lubricant and be equipped with a transmission oil cooler.
 - F. Steering: Hydraulic actuated power steering as regularly offered by manufacturer.
 - G. Front Axle: I Beam Type with wet seals, outboard mounted drums and a minimum capacity of 8,000 pounds.

- H. Rear Axle: Single speed full-floating type with wet seals, outboard mounted drums and a minimum capacity of 17,500 pounds. Ratio of 4.56, 4.63, 4.78, or 4.88 to 1. Alternate ratio may be provided if approved by AHTD prior to delivery. (Axle ratio should provide a maximum theoretical geared speed of no less than 69 MPH and still provide acceptable startability.)
 - I. Springs: As required to meet GVWR and axle ratings specified above.
 - J. Air System: Air compressor shall have a minimum capacity of 12.9 cfm and draw air through the engine air cleaner. Air system shall be equipped with a heated air dryer.
 - K. Brakes: Factory installed full air operated two shoe type with automatic slack adjusters and dust shields on front and rear. Rear brakes shall have spring set parking brakes.
 - L. Frame: Section modulus and yield strength of frame material shall provide a minimum RBM of 600,000. If the aerial lift manufacturer requires a stronger frame or additional frame reinforcement, it shall be provided. It shall be the responsibility of the successful bidder to insure that any additional frame requirements which may be needed for proper installation of the aerial lift and body are provided (i.e. – after frame length, frame reinforcement, clean CA or clear frame rails).
 - M. Cab: Conventional cab as regularly furnished by manufacturer, complete with insulation and all interior trim. Cab glass shall include windshield, roll-up windows in doors and rear cab glass as a minimum. Shall have key type locks on doors, factory installed fresh air heater-defroster unit, grab handle on each side, right and left sun shades and fitted rubber floor mats.
 - (1) Instruments: Shall include the following as a minimum:
 - (a) Speedometer/odometer
 - (b) Electric tachometer
 - (c) Electric engine hour meter
 - (d) Ammeter or volt meter
 - (e) Oil pressure gauge
 - (f) Coolant temperature gauge
 - (g) Transmission oil temperature gauge or warning light
 - (2) Cruise Control: Factory installed electronic cruise control.
 - (3) Air Conditioning: Factory installed air conditioning. Shall include tinted glass all around.
 - (4) Windshield Wipers: Dual electric intermittent windshield wipers with washers.
 - (5) Seats: Three (3) person seating, including seat belts, consisting of an air suspension driver's seat and a two (2) person passenger seat.
 - (6) Radio: Factory installed electronic AM/FM radio.
 - (7) Mirrors: Dual West Coast Sr. type mirrors no less than 7" x 16" with adjustable brackets and auxiliary convex mirrors.
 - (8) Air Horn: Single or dual-trumpet air horn.
 - N. Wheels: Seven (7) 19.5" hub piloted steel disc with no less than 7.50" rim section. Rear wheels to be dual.
 - O. Tires: Six (6), no less than 245/70R19.5 - G load range, tubeless steel belted radial; Two (2) Front and Four (4) Rear.
 - P. Fuel Tank(s): Single or dual fuel tanks with instrument panel fuel gauge. Minimum fuel capacity of 35 gallons.
 - Q. Hood: Tilting fiberglass or composite hood and fenders.
 - R. Lights: Shall be equipped with dual beam headlights, parking lights, clearance lights, automatic backup lights, directional turn signals with column mounted switch and hazard flasher switch. Rear signals to be wired for stop and tail lights in addition to directional signals.
 - S. Backup Alarm: Shall be equipped with an electric backup alarm meeting the requirements of SAE J994 with a minimum sound level output of 97 decibels.
6. Color: Truck cab, aerial lift, service body and sign storage compartment shall be painted Sherwin Williams F8W2030 Frost White Acrylic Enamel, or approved equal. Front bumper, grill, mirrors and wheels as regularly furnished by manufacturer.

7. Warranty:
- A. Cab and chassis shall have truck manufacturer's regular warranty. Warranty data shall be furnished with each unit. The Warranty Data shall contain all necessary information such as motor and/or serial numbers and shall be signed by the selling dealer at the time vehicle is delivered to the Highway Department.
 - B. Aerial lift, service body, sign storage compartment and other incidental equipment purchased under this specification shall be warranted against defective material and workmanship for a minimum period of twelve (12) months (365 Days) from date unit is placed in operation by AHTD. In addition, manufacturer's standard warranty period on components that exceeds the 12 months warranty shall remain in effect.
 - (1) Warranty shall include all parts, labor and transportation costs to the location of equipment.
 - (2) If equipment cannot be repaired on location, warranty shall include cost of transport to the facility where the repair work will be done.
 - (3) It will be the responsibility of the successful bidder to insure that repairs are completed in a timely manner.
 - C. If any warranty literature submitted with the bid conflicts with AHTD warranty requirements, the conflict(s) shall be specifically noted, corrected and included with the bid or the conflict(s) will be considered an exception to warranty specifications and the bid rejected.
 - D. Recent prior failure to provide warranty-work, parts, replacement parts or service, in a timely manner, for equipment from the same manufacturer or dealer shall be grounds for the rejection of any submitted bid, or for the denial of any otherwise qualified low bidder, whether such failure is attributable to the manufacturer or the dealer of the equipment. For the purposes of this paragraph "timely manner" means a period of time not exceeding thirty (30) calendar days to provide requested warranty-work, parts, replacement parts, or service. For the purposes of this paragraph "manufacturer" means the original manufacturer of the equipment and its successor or successors, regardless of number, and whether acquired by sale, merger, or otherwise. For the purposes of this paragraph "replacement part" means a part redesigned by a manufacturer to correct a design or engineering defect and which replacement part is capable of providing dependable performance in normal operation conditions for its normal service life without failure. Such bid or bids may be rejected by the Department until such failure or failures have been remedied to the satisfaction of the Department and until such manufacturer or dealer is providing such warranty-work, parts, replacement parts, and service in a timely manner.
8. Current Model: Units furnished under this specification shall be the latest improved model in current production, as offered to commercial trade, built for the U.S. market, and shall be of quality workmanship and material. Machines manufactured for foreign markets will not be accepted. All equipment offered under this specification shall be new. Used, reconditioned, shopworn, demonstrator, prototype or discontinued models are not acceptable. Manufacturers of the units supplied must have been in the business of producing operational units for at least two years and must have recently sold similar units to domestic governmental agencies. The model furnished must have been in production for a minimum of one year, or be the latest version of a previous model. Bidder/s may be required to submit documentation substantiating the aforementioned requirements. A list of user references may also be required.
9. Manuals, Certificate of Origin and Invoice:
- A. The successful bidder shall furnish an Operator's Instruction Manual for the aerial lift and for the truck with each unit delivered. One (1) copy each of Shop Repair Manual and Parts Book for the aerial lift and one (1) copy of Shop Repair Manual for the truck shall be furnished to each FOB point. In addition, one (1) copy each of Operator's Instruction Manual, Shop Repair Manual, and Parts Book for the aerial lift shall be furnished to Equipment & Procurement Division, P.O. Box 2261, Little Rock, AR 72203 (11302 W. Baseline Road, Little Rock, AR 72209, if shipping UPS, FedEx, etc.).
 - B. Certificate of Origin, Federal Excise Tax Exemption Certificate, Odometer Disclosure Statement and Five (5) copies of the Invoice to be furnished to Equipment & Procurement Division, P.O. Box 2261, Little Rock, AR 72203 (11302 W. Baseline Road, Little Rock, AR 72209, if shipping UPS, FedEx, etc.).
 - C. The successful bidder may provide Shop Repair Manuals and Parts Manuals on computer media (CD ROM, Floppy Disks, etc.) in lieu of printed manuals.
10. Training: The successful bidder shall furnish qualified personnel to instruct AHTD operators and service technicians on operation and maintenance of units purchased under this specification.

11. Unit shall be assembled, adjusted and made ready for continuous operation at time of delivery.

All equipment and accessories necessary for efficient operation of unit shall be furnished even though they are not specifically mentioned in this specification. This shall include any reinforcements or modifications to frame or to service body which may be required for proper installation of unit.

Aerial lift furnished shall meet applicable ANSI standards.


12. Parts Inventory & Service Facilities: The successful bidder shall maintain a representative inventory of replacement parts and service facilities for servicing equipment bid on.
13. Demonstration: The Arkansas State Highway & Transportation Department reserves the right to require a demonstration, under actual working conditions, of equipment bid under this specification before award is made. The demonstration would be performed (free of any charge) by the bidder or an authorized representative at a mutually acceptable location. If requested, the bidder should be prepared to demonstrate the equipment within thirty (30) days after notification. Failure of the bidder to perform a satisfactory demonstration within the specified time may be grounds for rejection of the bid.
14. Cooperative Purchasing: Other tax-supported entities* in Arkansas (cities, counties, state agencies, school districts, etc.) may purchase from this Contract on an individual basis under the same specifications and conditions, and at the pricing set forth by each vendor, all at the discretion of each vendor in each case. Prices could be reduced by a vendor for minor alterations in conditions (changing order quantities, deleting options, etc.) as agreed by both parties, but could not be raised above the contract bid price except for any additional freight charges. Vendors would not be required to sell to any such entity under this contract, and those entities would not be obligated to purchase from the contract.

Each entity wishing to purchase from the contract must make contact directly with the appropriate vendor(s). The Highway Department shall remain "out of the loop" for such transactions: all contact, orders, invoices, payments, etc. regarding such transactions must take place exclusively between the tax-supported entity and the vendor. The Department shall be held harmless of any and all liability arising from such transactions.

* Tax-supported entities are defined as those receiving more than half of total funding from appropriated tax funds.



ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT
SPECIFICATION 09-64-9100

Rotating Metal
Platform In Lieu Of
Fiberglass Bucket



**TRUCK MOUNTED AERIAL LIFT AND BODY
WITH SIGN STORAGE COMPARTMENT**


DRAWING NOT TO SCALE



(22) 1/8" x 1" x 1" ANGLES
 SPOT WELDED & RIVETED
 IN PLACE RUNNING LENGTH
 OF BOX FOR PARTITIONS
 FOR SIGN STORAGE.
 LOCATED TOP & BOTTOM.
 44 ANGLES REQ'D.

NOTE: SEE ISOMETRIC VIEW FOR DOOR DETAILS

NEOPRENE RUBBER
 GASKET ALL AROUND
 FOR WATERPROOF
 DOOR SEAL. TYP.
 BOTH ENDS.



ISOMETRIC VIEW
 CURB SIDE VIEW SHOWN,
 TYP. STREET SIDE OPPOSITE END

ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT
 SPECIFICATION 09-64-9100

SIGN STORAGE BOX

DRAWING NOT TO SCALE